



Addendum No. 1

**City of Coquitlam
Tender No. 77579-2
Guildford Greenway - Phase 2
(Consists of 5 Pages)**

Issue Date: May 7, 2024

Tenderers shall note the following changes:

REVISIONS:

1. REFER to FORM OF TENDER

REMOVE: **Appendix 1**

REPLACE WITH: ***Revised* - Appendix 1 - *Revision No. 1***

2. REFER to Supplementary Contract Specifications

SECTION 32 17 23S (PAINTED PAVEMENT MARKINGS)

ADD New Clause 1.5.5.1:

Relocation of the existing Park Information Sign will be considered incidental to work in other sections.

SECTION 32 31 13S (CHAIN LINK FENCES AND GATES)

ADD New Clause 1.5.5

Relocation of existing bollards will be considered incidental to work in other sections.

QUESTIONS AND CLARIFICATIONS:

Q1.) The 'Combined Drawings' pdf is missing sheets 4-6 (Pinetree Way traffic signal) in the DMD drawing package (starts on page 24).

A1.) Please refer to the Supplementary Contract Specifications, Section 00 72 43S, sub-section 1.02: The Guildford Way and Pinetree Way intersection electrical drawings will be provided during the tender process.

Q2.) Could you please clarify if CB01 and CB03 are existing or new?

A2.) All of the catch basins, regardless of the type, are proposed unless otherwise noted on the Contract Drawings.

Q3.) Item 9.03 CB removal & disposal 21 each, my takeoff is 29 each, could you please address this item?

A3.) Refer to FORM OF TENDER: *Revised* - Appendix 1 - *Revision No. 1*, Pay Items 9.03.

Q4.) Bid item 21.07 indicates 5 CB adjustments, my takeoff shows 7, please clarify.

A4.) Refer to FORM OF TENDER: *Revised* - Appendix 1 - *Revision No. 1*, Pay Items 20.07.

Q5.) Bid item 4.05 indicates 115 LM of Band curb, my takeoff shows 193, please clarify.

A5.) Refer to FORM OF TENDER: *Revised* - Appendix 1 - *Revision No. 1*, Pay Items 4.05.

Q6.) Which bid item should the sod removal & disposal ($920\text{m}^2 \times 0.3\text{m} = 276\text{m}^3$) be in?

A6.) Sod removal and disposal will be paid for under line item 9.04 – Common Excavation (Incl. Offsite Disposal).

Q7.) Please clarify which bid item “ADJUST EX. CHAMBER TO FINAL GRADE (TYP.)” is to be included in.

A7.) We will install the new sidewalk/bike lane so it works with the current grade of the chambers.

Q8.) Please clarify which bid item “RELOCATE BIKE LOCKER” is to be included in.

A8.) The existing bike locker will be relocated by others.

Q9.) Please clarify which bid item “RELOCATE EXISTING BOLLARDS TO BACK OF NEW TYPE E CURB (TYP.)” is to be included in.

A9.) Refer to Supplementary Contract Specifications, revised Section 32 31 13S, Sub-Section 1.5.5.

Q10.) Please clarify which bid item "RELOCATE PARK INFORMATION SIGN" is to be included in.

A10.) Refer to Supplementary Contract Specifications, revised Section 32 17 23S, Sub-Section 1.5.5.1.

Q11.) Could you please label the trees to be removed and / or relocated, after printing the drawing with heavyweight line types, we are unable to clearly identify these trees. I understand tree removal is bid item 7.01, which bid item would include tree relocation?

A11.) All trees marked for removal on the Contract Drawings are to be removed. The Sequoia tree at the northwest corner of Pinetree Way and Guildford Way is the only tree to be relocated, which will be done by others.

Q12.) Please clarify if the Tactile Warning tiles are surface applied, cast in place, or tactile pavers.

A12.) Please refer to the Supplementary Contract Specifications Section 03 30 20S, Sub-Section 2.1.7: The tactile warning surface tiles shall be replaceable cast-in-place style.

Q13.) There is a line item for eradication but from the roadworks/pacing limits don't show any. Please confirm if this item is required and confirm where the eradication would need to be completed.

A13.) Line painting eradication and temporary pavement markers are required to ensure safe lane widths are maintained during construction and after hours. The Contractor is required to ensure safe travel for vehicles during construction.

Q14.) There is a line item for removal of one cat eye reflector but we don't see it on the drawings. Please confirm if this will be required and confirm where on the drawings we can find it.

A14.) There are recessed snowplowable reflective pavement markers (cat-eye) along the centre lines of the road on Guildford Way, which need to be eradicated. These will be paid for as a lump sum amount. Please refer to FORM OF TENDER – Appendix 1.

Q15.) Note #2 on Dwg. No. 04 of 22 on the civil drawings for the Bus Stop Barrier Fence Section Detail says "All components to be stainless steel", however the Tender Forms,

item 15.01 and page 101 of the contract documents state that the bus stop barrier fence is MMCD C14 powder coated black. Please confirm which is correct and if there are any other components the Contractor should be made aware of that are to be stainless steel.

A15.) The Bus Stop Barrier Fence is to be MMCD C14 powder coated black. The mounting components are to be stainless steel.

End of Addendum No. 1

Tenderers shall take into account the content of this Addendum in the preparation and submission of the Tender which will form part of the contract and shall be acknowledged on the Tender Form, Item 1.

Upon submitting a Tender, Tenderers will be deemed to have received notice of all Addenda that are posted on the City's website and deemed to have considered the information for inclusion in the Tender submitted.

Issued by:

Mark Pain
Procurement Manager

Email: bid@coquitlam.ca

Revised - APPENDIX 1 - Revision No. 1
FORM OF TENDERContract 77579-2
Guildford Greenway - Phase 2**SCHEDULE OF QUANTITIES AND PRICES**

(see paragraph 5.3.1 of the Instruction to Tenderers)

(All Tender and Contract Prices shall NOT include GST. GST will apply upon payment)**(Should there be any discrepancy in the information provided, the City's original file copy shall prevail)**

ITEM NO.	MMCD Ref./ (Supplementary Contract Specifications)	DESCRIPTION	UNIT	QTY	UNIT PRICE	EXTENDED AMOUNT
1.00	01 55 005	TRAFFIC CONTROL, VEHICLE ACCESS AND PARKING				
1.01	(1.5.1)	Traffic Control and Management				Incidental to Contract
2.00	01 57 015	ENVIRONMENTAL PROTECTION				
2.01	(1.6.1)	ESC supply & Installation, Maintenance and Removal				Incidental to Contract
3.00	01 58 015	PROJECT IDENTIFICATION				
3.01	(1.3.1)	1.2m x 1.2m Static Construction Zone Information Sign	ea.	5		
3.02	(1.3.2)	Changeable Message Signs (CMS) (x2)	month	5		
4.00	03 30 205	CONCRETE WALKS, CURBS AND GUTTERS				
4.01	(1.4.3)	Concrete Barrier Curb and Gutter (MMCD C4) (Incl. Gravels)	lin.m	1,527		
4.02	(1.4.3)	Concrete Barrier Curb and Gutter (MMCD C5) (Incl. Gravels)	lin.m	235		
4.03	(1.4.3)	Concrete Type E Bike/Pedestrian Mountable Separation Curb with Gutter (Incl. Gravels)	lin.m	1,193		
4.04	(1.4.3)	Retrofit Concrete Type E Bike/Pedestrian Mountable Separation Curb with Gutter (Incl. Gravels) (Sheet 03 of 22)	lin.m	143		
4.05	(1.4.3)	150mm Wide Concrete Band/Curb	lin.m	193		
4.06	(1.4.5)	Concrete Sidewalk, Wheelchair Letdowns, Ramps, Medians, & Bus Shelter Pads - 100mm thick - Broom Finished (Incl. Gravels); and as shown and described in the Contract Documents	sq.m	2,800		
4.07	(1.4.5)	Concrete Driveway Letdown - 190mm thick - Broom Finished (Incl. Gravels); and as shown and described in the Contract Documents	sq.m	60		
4.08	(1.4.5)	Stamped Concrete Buffer Zones (Incl. Gravels)	sq.m	780		
4.09	(1.4.5)	Raised Concrete Islands at Protected Intersections	sq.m	125		
4.10	(1.4.10)	Tactile Directional Indicators - 1.2m Wide x 1.5m Long - Elongated Bars with Flat Top Pattern	sq.m	10		
4.11	(1.4.10)	Tactile Attention Indicators - 0.6m Wide - Truncated Domes Pattern	lin.m	287		
4.12	(1.4.10)	Tactile Directional Indicators - 0.6m Wide - Elongated Bars with Flat Top Pattern	lin.m	32		
5.00	03 40 01	PRECAST CONCRETE				
5.01	1.4.1	High Profile Parking Curb (c/w Rebar Pins)	ea.	13		
5.02	1.4.2	Allan Block Retaining Wall Behind Bus Stops/Sidewalk (approx. 300mm high) - Provisional	sq.m	20		
6.00	26 56 015	ROADWAY LIGHTING				
6.01	(1.9.1)	Supply, Installation and Relocation of Roadway and Pedestrian Lighting (ALL) Works Including any removal, adjustments and disposal needed to complete the work and as shown on the Contract Drawing	L.S.	1		
7.00	31 11 015	CLEARING AND GRUBBING				
7.01	(1.4.1)	Tree/Hedge Trimming and Removal (Incl. Offsite Disposal)	L.S.	1		
8.00	31 11 415	SHRUB AND TREE PRESERVATION				
8.01	(1.3.2)	Hydro Excavation		Allowance	\$20,000.00	\$20,000.00
9.00	31 24 135	ROADWAY EXCAVATION, EMBANKMENT AND COMPACTION				
9.01	(1.8.4)	Remove and Dispose of Existing Concrete or Asphalt Flat Work (Incl. Offsite Disposal)	sq.m	7200		
9.02	(1.8.4)	Remove and Dispose of Existing Concrete Curb & Gutter (Incl. Offsite Disposal)	lin.m	1800		
9.03	(1.8.4)	Remove Catchbasin (Incl. Offsite Disposal)	ea.	29		
9.04	(1.8.5)	Common Excavation (Incl. Offsite Disposal)	cu.m	1450		
10.00	32 01 11	PAVEMENT SURFACE CLEANING AND REMOVAL OF PAVEMENT MARKINGS				
10.01	1.2.3	Line Painting Eradication (as shown on Contract Drawings)	L.S.	1		
10.02	1.2.3	Recessed Snowplowable Pavement Marker Removal (Cat-Eye Only)	L.S.	1		
11.00	32 01 16.75	COLD MILLING				
11.01	(1.5.4)	Inlay Milling (Up to 50mm)	sq.m	10620		
12.00	32 11 235	GRANULAR BASE				
12.01	(1.4.3)	19mm Minus Granular Base - Provisional	tonne	100		
13.00	32 12 165	HOT-MIX ASPHALT CONCRETE PAVING				
13.01	(1.5.1)	Asphaltic Concrete Paving - Road Restoration - Lower Course #1 (65mm thick) (Incl. Gravels)	tonne	225		
13.02	(1.5.1)	Asphaltic Concrete Paving - Road Restoration - MOT Class 1 Medium Mix with 80-100 Group A Asphalt Binder (50mm thick)	tonne	1,480		
13.03	(1.5.3)	Asphaltic Concrete Paving - Separated Bike Lane - Upper Course #2 (50mm, 1 lift) (Incl. Gravels)	tonne	310		
14.00	32 17 235	PAINTED PAVEMENT MARKINGS				
14.01	(1.5.3)	Permanent Thermoplastic Pavement Markings (incl. Bicycle Symbols)	L.S.	1		
14.02	(1.5.2)	MMA Solid Green Conflict Zone Painting	L.S.	1		
14.03	(1.5.4)	Supply and Install Traffic Signage on New Base and Post (City to Supply New Sign Tabs)	ea.	53		
14.04	(1.5.4)	Relocate Existing Traffic Signage (Incl. Pole and Base)	ea.	24		
14.05	(1.5.5)	Steel Flex Delineators (c/w Object Marker Reflective Tape)	ea.	1		
14.06	(1.5.5)	Steel Flex White Delineators (c/w White Reflective Markings)	ea.	7		
14.07	(1.5.6)	Bus Bench Relocation	ea.	4		
15.00	32 31 135	CHAIN LINK FENCES AND GATES				
15.01	(1.5.4)	Bus Stop Barrier Fence - Attached Mounting (MMCD C14 Powder Coated Black)	lin.m	33		
16.00	32 91 215	TOP SOIL AND FINISH GRADING				
16.01	(1.4.1)	Topsoil (150mm)	cu.m	110		
17.00	32 92 195	HYDRAULIC SEEDING				
17.01	1.8.2	Hydraulic Seeding (Restoration)	sq.m	390		
18.00	32 92 235	SODDING				
18.01	(1.8.1)	Sodding (New Boulevards)	sq.m	310		
19.00	33 40 015	STORM SEWERS				
19.01	(1.6.5)	Catchbasin Leads c/w tie-in - 150mm SDR28 PVC (incl. Backfill and Permanent Trench Restoration - COQ-G4)	lin.m	88		
19.02	(1.6.5)	Catchbasin Leads c/w tie-in - 200mm SDR35 PVC (incl. Backfill and Permanent Trench Restoration - COQ-G4)	lin.m	9		
20.00	33 44 015	MANHOLES AND CATCHBASINS				
20.01	(1.5.2)	Top Inlet Catchbasin Assembly	ea.	30		
20.02	(1.5.2)	ACO Klassik K1 Series 900 4" Wide In-Line Catch Basin Assembly, c/w 0.5m Channel and 1.0m Mesh Steel Grate (Type 430D - Stainless) (for Type E Curb and Gutter)	ea.	18		
20.03	(1.5.2)	Side Inlet Catchbasin Assembly (COQ-S11A)	ea.	6		
20.04	(1.5.3.1/1.5.4)	Manhole Adjustment Only - Provisional	ea.	22		
20.05	(1.5.3.2/1.5.4)	Water Valve Box Adjustment Only - Provisional	ea.	15		
20.06	(1.5.3.2)	Water Valve Box Replacement and Adjustment - Provisional	ea.	5		
20.07	(1.5.3.3/1.5.4)	Catch Basin Adjustment Only	ea.	7		
20.08	(1.5.3.4)	Junction Box Adjustment Only (5686 Service Box)	ea.	29		
21.00	34 41 135	TRAFFIC SIGNALS				
21.01	(1.9.2)	Traffic Signal Modifications and Bike Signal Activation (ALL) - Pacific Street Intersection- as shown on the Contract Drawings	L.S.	1		
21.02	(1.9.2)	Traffic Signal Modifications and Bike Signal Activation (ALL) - Town Centre Boulevard Intersection - as shown on the Contract Drawings	L.S.	1		
21.03	(1.9.2)	Traffic Signal Modifications and Bike Signal Activation (ALL) - Pinetree Way Intersection - as shown on the Contract Drawings	L.S.	1		
21.04	(1.9.4)	Supply and Installation of Detector Loops	ea.	14		

Total Tendered Price (exclude GST): \$

(Transfer the amount to Form of Tender Summary Page 1)

Name of Contractor: _____